

CITY OF OAKDALE PUBLIC WORKS DEPARTMENT

455 South Fifth Avenue • Oakdale, CA 95361 • Ph: (209) 845-3600 • Fax: (209) 848-4344

**CITY
ADMINISTRATION
& FINANCE
DEPARTMENT**
280 N. Third Ave.
Oakdale, CA 95361
(209) 845-3571
(209) 847-6834 Fax

**COMMUNITY
DEVELOPMENT
DEPARTMENT**
455 S. Fifth Ave.
Oakdale, CA 95361
(209) 845-3625
(209) 845-8903 Fax

FIRE DEPARTMENT
Station No. 1:
325 East "G" St.
Station No. 2:
450 S. Willowood Dr.
Oakdale, CA 95361
(209) 845-3660
(209) 847-5907 Fax

**PARKS & RECREATION
DEPARTMENT**
325 East "G" St.
Oakdale, CA 95361
(209) 845-3591
(209) 845-3692

POLICE DEPARTMENT
245 N. Second Ave.
Oakdale, CA 95361
(209) 847-2231
(209) 847-3790 Fax

**CITY OF OAKDALE
WEBSITE**
www.ci.oakdale.ca.us
E-MAIL
info@ci.oakdale.ca.us

September 15, 2026

The City of Oakdale invites you to bid on the following project:
South Avenue Roadway Project (Project #26-006)

Location: South Ave, Oakdale CA 95361

(South Ave and South Yosemite, South Ave and South Sierra Ave)

Project Timeline:

Work to begin: October 12, 2026

Work to be completed: The project shall be completed within 30 working days from the start date.

Detailed Specifications:

South Avenue Paving Project – Scope of Work

The Contractor shall furnish all labor, materials, equipment, traffic control, and incidentals necessary to complete the South Avenue roadway improvements in accordance with City of Oakdale standards and specifications. See the attached South Avenue project map and City standards for additional project limits, details, and requirements.

The scope of work shall include:

- **Demo & Grade Roadway:** Prepare approximately 19,090 SF of existing roadway, including demolition, grading, shaping, and preparation of the roadway surface for paving.

- **Roadway Paving – Grind and Overlay:** Grind the existing roadway surface as necessary and furnish and place approximately **19,090 SF of 4-inch HMA pavement**, including surface preparation, proper placement, compaction, joints, transitions, and finished grades in accordance with City of Oakdale standards.
- **Compaction Restrictions:** No vibratory compaction equipment shall be permitted due to the presence of existing transite pipe beneath the roadway. All compaction shall be performed using non-vibratory methods to prevent damage to the existing pipe.
- **Raise Valve Boxes & Manholes:** Adjust and raise seven **(7)** existing valve boxes and/or manholes to match the final pavement elevation.
- Protect existing utilities, curb, gutter, sidewalk, driveways, and other improvements that are to remain.
- Provide all necessary traffic control and maintain reasonable access to adjacent properties during construction.
- Remove and properly dispose of all demolition materials and construction debris.
- Upon completion, the roadway shall have a smooth and uniform finished surface with positive drainage and shall be completed to the satisfaction of the City of Oakdale.

Contractor Requirements: Contractors must possess a valid Class A – General Engineering Contractor license issued by the California Contractors State License Board.

Engineer's Estimate: No Engineer's Estimate is available for this project.

Mandatory Job Walk: None

Bids exceeding \$25,000 will require a Bid Bond of 10% of bid amount. A Payment Bond will be required after project award and before work begins. BIDS WILL NOT BE ACCEPTED WITHOUT BID BONDS.

COMPLIANCE MONITORING

This project is subject to compliance monitoring and enforcement by the Department of Industrial Relations, Office of the Labor Commissioner.

PUBLIC WORKS PROJECT AWARD NOTIFICATION

The PWC 100 form should be completed on-line by the Awarding Body (City of Oakdale). The completion and the submission of this form fulfills the required public works project notification to both the Division of Apprenticeship Standards (Labor Code sec 1773.3 (replacing former DAS 13 notification) and the Division of Labor Standards Enforcement Public Works Compliance Monitoring Unit {8 Cal. Code Reg. sec. 16451 (a)}

CONTRACTOR REGISTRATION

In compliance with SB 854, no contractor or subcontractor may be listed on a bid proposal for a public works project (submitted on or after March 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5 [with limited exceptions from this requirement for bid purposes only under Labor Code section 1771.1(a)]. In addition, no contractor or subcontractor may be awarded a contract for public work on a public works project (awarded on or after April 1, 2015) unless registered with the Department of Industrial Relations pursuant to Labor Code section 1725.5.

CERTIFIED PAYROLL

All contractors and subcontractors must furnish electronic certified payroll records directly to the Labor Commissioner (aka Division of Labor Standards Enforcement).

For all new projects awarded on or after April 1, 2015, the contractors and subcontractors must furnish electronic certified payroll records to the Labor Commissioner.

As of January 1, 2016, the requirement to furnish electronic certified payroll records to the Labor Commissioner will apply to all public works projects, whether new or ongoing.

These requirements apply to all public works that are subject to prevailing wage requirement of the Labor Code without regard to funding source.

DISPOSAL OF MATERIALS: Construction and demolition debris and other waste materials generated by the work shall be transported to and delivered to a facility or operation legally authorized to receive the specific material. Contractor shall comply with all applicable federal, state, and local requirements governing transportation, recycling, processing, and disposal. Upon request by the City, Contractor shall provide disposal, recycling, weight tickets, receipts, or other documentation sufficient to demonstrate lawful disposition of the material.

INSURANCE

\$2,000,000 General Liability and Automobile Liability Insurance will be required. Workers Compensation Insurance with limits of at least one million (\$1,000,000) will also be required along with a Waiver of Subrogation endorsement in favor of City, its officers, agents, employees, and volunteers. Certificates of insurance to be provided when bid is awarded.

Bids shall be received by Manuel Lopez via email at mlopez@oakdaleca.gov or hand delivered to 455 South 5th Avenue, Oakdale, CA 95361, up to no later than **2:00 p.m. on September 24, 2026**. No bids will be accepted after this time.

Please contact Manuel Lopez for additional information or questions regarding this project at (209) 845-3619.

INFORMAL BID – South Avenue Pavement Improvements

Please provide the following pricing/ quote for this project:

1. \$ _____

Signature

Date

Company Name

License #


DIR #

Email


Please be sure the following are included with your bid. Bids will not be accepted without the following:


- Informal Bid Sheet (this document)
- Proof of Insurance that meets the minimum requirements
- Bid Bond
- Active Contractors License
- Active DIR Registration

South Ave & South Yosemite Ave



South Ave & South Sierra Ave





NOTES:

1. SEE SECTION 3 OF SPECIFICATIONS FOR APPROVED MATERIALS.
2. USE VALVE EXTENSION ON OPERATING NUTS DEEPER THAN 48". EXTENSION SHALL BE A PLACER WATERWORKS "RECYCLED WATER VALVE STEM EXTENSION" OR APPROVED EQUAL.

APPROVED BY CITY COUNCIL:
RESOLUTION: 2025-094

Rob Marler

ROB MARLER, P.E. - CITY ENGINEER


WATER VALVE BOX

CITY OF OAKDALE
DEPARTMENT OF PUBLIC SERVICES

DATE: 09-15-25

DRAWING NO.

3-A



NOTES:

1. 2" TO 3" GRADE ADJUSTING RINGS REINFORCED AS REQUIRED.
2. STANDARD CONCENTRIC CONE SHALL CONFORM TO ASTM C418-61T.
3. STANDARD PRE-CAST MANHOLE SECTIONS SHALL CONFORM TO ASTM C418-61T.
4. BOTTOM OF MANHOLE SHALL BE CONSTRUCTED FROM FLOWLINE TO FLOWLINE AND SHAPED TO CONFORM WITH THE DIAMETER OF THE PIPE AND DIRECTION OF FLOW.
5. GROUT ALL JOINTS. RUBBER GASKET, BELL SPIGOT BARRELS PREFERRED, OR USE "RAM NEK" OR APPROVED EQUAL.
6. MANHOLE COVER TO BE MARKED "SEWER".
7. ADJUST FRAME TO GRADE AFTER PAVING.

APPROVED BY CITY COUNCIL:
RESOLUTION: 2025-094

Rob Marler

ROB MARLER, P.E. - CITY ENGINEER

SEWER MANHOLE

CITY OF OAKDALE
DEPARTMENT OF PUBLIC SERVICES

DATE: 09-15-25

DRAWING NO.

4-C

)

)

)

That we, _____ of

the City of _____, County of _____ and _____

State of _____ (hereinafter called Principal) as

Principal, and

(hereinafter called Surety) as Surety, authorized under the laws of the State of

to act as Surety on bonds for Principals, are held and firmly bound unto the

(hereinafter called Obligee) as Obligee, in the penal sum of

DOLLARS)

(\$

Dated this _____ day of _____, 20____

Contract with Obligee for Construction of

The Surety, for value received, hereby stipulates and agrees that the obligations of said Surety and its BOND shall be in no way impaired or affected by any extension of the time within which the OWNER may accept such BID; and said Surety does hereby waive notice of any such extension.

IN WITNESS WHEREOF, the Principal and the Surety have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers, the day and year first set forth above.

Principal (L.S.)

Surety

By: _____

IMPORTANT - Surety companies executing BONDS must appear on the Treasury Department's most current list (Circular 570 as amended) and be authorized to transact business in the state where the project is located.